



Coastal
The Energy People

April 12, 2001

Ms. Lisha Cordova
State of Utah
Division of Oil Gas & Mining
1594 West North Temple, Suite 1210
Salt Lake City, Utah 84114
Attn: Lisha Cordova

RE: NBU # 336
Sec. 4-T10S-R22E

Dear Ms. Cordova:

Enclosed is the APD for the location listed above. Please do not hesitate to call me if you have any questions, or need additional information at (435) 781-7021.

Holly Miner

Holly Miner
Assistant Regulatory Analyst

RECEIVED

APR 13 2001

DIVISION OF
OIL, GAS AND MINING

Coastal Oil & Gas Corporation

A SUBSIDIARY OF THE COASTAL CORPORATION
1368 S 1200 E • P.O. BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

Form 3160-3
(August 1999)FORM APPROVED
OMB No. 1004-0136
Expires November 30, 2000UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER



1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. U-01191
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator COASTAL OIL & GAS CORPORATION CONTACT: CHERYL CAMERON OPERATIONS EMAIL: Cheryl.Cameron@CoastalCorp.com		7. If Unit or CA Agreement, Name and No.
3a. Address P.O. BOX 1148 VERNAL, UT 84078	3b. Phone No. (include area code) TEL: 435.781.7023 EXT: FAX: 435.789.4436	8. Lease Name and Well No. NBU #336
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface LOT #2 NWNE 515FNL 2134FEL At proposed prod. zone 4426 917 N 632992 E		9. API Well No. 43-047-34627
10. Field and Pool, or Exploratory NATURAL BUTTES		11. Sec., T., R., M., or Blk., and Survey or Area Sec 4 T10S R22E UBM
12. Distance in miles and direction from the nearest town or post office* 26.7 MILES SOUTHEAST OF OURAY, UTAH		12. County or Parish UINTAH
13. State UT		14. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. Unit line if any) 515
15. Distance from proposed location* to nearest well, drilling, completed, Applied for, on this lease, ft.		16. No. of Acres in lease 1041.7
17. Spacing unit dedicated to this well		18. Distance from proposed location* to nearest well, drilling, completed, Applied for, on this lease, ft.
19. Proposed Depth 7000 MD		20. BLM/BIA Bond No. on file U-605382-9
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5048 GL		22. Approximate date work will start*
23. Estimated duration		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) CHERYL CAMERON	Date 4/12/01
Approved by (Signature) 	Name (Printed/Typed) BRADLEY G. HILL	Date 04-18-01
Title RECLAMATION SPECIALIST III		

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States and false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.


*(Instructions on reverse)

ELECTRONIC SUBMISSION #3624 VERIFIED BY THE BLM WELL INFORMATION SYSTEM FOR COASTAL OIL & GAS CORPORATION
SENT TO THE VERNAL FIELD OFFICE**RECEIVED****APR 13 2001****DIVISION OF
OIL, GAS AND MINING****Federal Approval of this
Action Is Necessary**

T10S, R22E, S.L.B.&M.


COASTAL OIL & GAS CORP.

Well location, NBU #336, located as shown in Lot 2 of Section 4, T10S, R22E, S.L.B.&M., Uintah County, Utah.



BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN. NE QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
 REGISTRATION NO. 161319
 STATE OF UTAH

LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

UINTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 8-22-98	DATE DRAWN: 8-26-98
PARTY J.F. B.A. C.B.T.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE COASTAL OIL & GAS CORP.	

SEP 3 1998

COASTAL OIL & GAS CORP.SAB RAD SCP CEL
JBN MDE LPS

NBU #336

SECTION 4, T10S, R22E, S.L.B.&M.

RC: Only
R/L
P/B
D/S

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 6.9 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN LEFT AND PROCEED IN A NORTHERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN RIGHT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 4.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 7.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN LEFT AND PROCEED IN A NORTHERLY DIRECTION APPROXIMATELY 1.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN RIGHT AND PROCEED IN AN EASTERLY THEN NORTHEASTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE BEGINNING OF THE PROPOSED ACCESS ROAD TO THE NORTH; FOLLOW ROAD FLAGS IN A NORTHERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO PROPOSED LOCATION IS 40.7 MILES MORE OR LESS.

COMPANY NAME	Coastal Oil & Gas Corporation	DATE	March 20, 2001
WELL NAME	NBU #336	TD	7,000' MD/TVD
FIELD	NBU	COUNTY	Uintah
		STATE	Utah
		ELEVATION	5,055' KB
SURFACE LOCATION	515' FNL & 2134' FEL, Sec. 4, T10S, R22E	BHL	Straight Hole
OBJECTIVE ZONE(S)	Wasatch		
ADDITIONAL INFO			

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION	DEPTH	HOLE	CASING	MUD
	TOPS	(if required)	SIZE	SIZE	WEIGHT
		40'		14"	
			12-1/4"	8-5/8", 24#, K-55	Air
		250' MD/TVD			
	Green River @	1,340'			
Mud Log @ 2500' - TD					Air Mist
Platform Express			7-7/8"	4-1/2", 11.6#, K-55, LTC	Aerated Water
SC - TD					
	Wasatch @	4,420'			
		7,000' MD/TVD			

COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				2950	1370	263000
SURFACE	8-5/8"	0-250'	24.00	K-55	STC	21.03	11.71	4.70
						5350	4960	180000
PRODUCTION*	4-1/2"	0-TD	11.60	K-55	LTC	2.17	1.36	1.37

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
- 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
- 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
- (Burst Assumptions: FG @ 8-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50,000 lbs overpull)

CEMENT PROGRAM


		FT. OF FILL	DESCRIPTION	SACKS	EXCESS*	WEIGHT	YIELD
SURFACE		250	Class G + 2% CaCl ₂ + 0.25 lb/sk Cello Flake	90	35%	15.80	1.17
PRODUCTION	LEAD	3,920'	Hifill Mod. +16% gel + 3% salt + 10#/sk gilsonite + 1% HR7 + 0.6% Econolite + 0.2% FWCA + 0.25 lb/sk Flocele	430	50%	11.60	3.12
	TAIL	3,080'	50/50 POZ + 2% gel + 2% Microbond + 5% salt + 0.2% Super CBL + 0.6% HALAD 322 + 0.25 #/sk Flocele	850	50%	14.35	1.25

* or 15% over caliper log

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every other joint to surface with bow spring centralizers. Thread lock FE up to & including pin end of FC.
PRODUCTION	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every other joint to top of tail cement with bow spring centralizers.

WELLHEAD EQUIPMENT



TREE	2-1/16" 5M
TUBING HEAD	11" 3M X 7-1/16" 5M
CASING SPOOL	
CASING SPOOL	
CASING HEAD	8-5/8" SOW X 11" 3M

COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

BIT PROGRAM

ROCK BIT & PDC BIT PROGRAM						
INTERVAL	HOLE	BIT MFG & MODEL	GPM	SERIAL	NZLS	COMMENTS
Surface Hole	12-1/4"	Various				
Surf Csg - TD	7-7/8"	SEC XS44	Air/Mist	New	16-16-16	
			Aerated			

If the air is discontinued, use a SEC 2665rv or a HTC DP363 on a mud motor to TD

If a second bit is required and the air is needed use another XS44.

GEOLOGICAL DATA

LOGGING:

Depth	Log Type
SC - TD	Platform Express

MUD LOGGER:

SC - TD

SAMPLES:

As per Geology

CORING:

NA

DST:

NA

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER		TREATMENT
			LOSS	VISCOSITY	
0-Trona (0 - +/-2,000')	Air/Mist	NA	NA		Polymer, Gel Gyp, Lime
Trona-TD (+/- 2,000' - TD)	Aerated Water	NA	NC	NA	Polymer, Gyp, Lime

After reaching TD, circulate hole until clean, then make a wiper trip. Report any bridges or fill encountered on trip.

After a successful wiper trip, chain out of the hole to log.

REPORT ALL LOSSES, INCLUDING SEEPAGE

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Run Totco survey every 500' from surface casing shoe to TD. Maximum allowable hole angle is 5 degrees.

Treat for corrosion as per plan.

DRILLING ENGINEER:

Christa Yin

DATE: _____

DRILLING MANAGER:

Darrell Molnar

DATE: _____

DRILLING DIRECTOR:

Steve Hayes

DATE: _____

NBU #336
NW/NE Lot 2, Sec. 4-T10S, R22E
UINTAH COUNTY, UTAH
LEASE #U-01191

ONSHORE ORDER NO. 1
COASTAL OIL & GAS CORPORATION

DRILLING PROGRAM

1. **Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
KB	5055'
Green River	1340'
Wasatch	4420'
TD	6500'

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1340'
Gas	Wasatch	4420'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment** (Schematic Attached)

Please see the Natural Buttes Unit Standard Operating Procedure (SOP).

4. **Proposed Casing & Cementing Program:**

Please see the attached Drilling Program.

5. **Drilling Fluids Program:**

Please see the attached Mud Program.

6. **Evaluation Program:**

Please see the attached Geological Data.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 6,500' TD, approximately equals 2,600 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 1,170 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

NBU #336
NW/NE Lot 2, Sec. 4-T10S-R22E
UINTAH COUNTY, UTAH
LEASE #U-01191

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

An onsite inspection was conducted for the NBU #336 on 2/16/01, for the subject well.

1. Existing Roads:

The proposed well site is approximately 26.7 miles southeast of Ouray, Utah. Directions to the location from Ouray, Utah:

Proceed in a westerly direction from Vernal, Utah, along U.S. Highway 40 approximately 14.0 miles to the junction of state highway 88; exit left and proceed in a southerly direction approximately 17.0 miles to Ouray, Utah; proceed in a southerly direction approximately 6.9 miles on the Seep Ridge Road to the junction of this road and an existing road to the east; turn left and proceed in an easterly direction approximately 5.0 miles to the junction of this road and an existing road to the north; turn left and proceed in a northerly direction approximately 0.3 miles to the junction of this road and an existing road to the northeast; turn right and proceed in a northeasterly direction approximately 4.8 miles to the junction of this road and an existing road to the south; turn right and proceed in a southerly, then southeasterly direction approximately 7.2 miles to the junction of this road and an existing road to the north; turn left and proceed in a northerly direction approximately 1.4 miles to the junction of this road and an existing road to the east; proceed in an easterly then northeasterly direction approximately 0.7 miles to the junction of this road and an existing road to the northwest; turn left and proceed in a northwesterly direction approximately 0.3 miles to the beginning of the proposed access road to the north; follow road flags in a northerly direction approximately 0.2 miles to the proposed location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

2. Planned Access Roads:

Please see the Natural Buttes Unit Standard Operating Procedure (SOP).

Refer to Topo Map B for the location of the proposed access road.

3. Location of Existing Wells Within a 1-Mile Radius:

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities:

Please see the Natural Buttes Unit SOP.

Refer to Topo Map D for the location of the proposed pipeline.

5. **Location and Type of Water Supply:**

Please see the Natural Buttes SOP.

6. **Source of Construction Materials:**

Please see the Natural Buttes SOP.

7. **Methods of Handling Waste Materials:**

Please see the Natural Buttes SOP.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec.5,T9S,R22E, NBU #159, Sec.35,T9S,R21E, Ace Oilfield Sec.2, T6S,R20E, MC&MC Sec 12, T6S,R19E (Requests is lieu of filing Form 3160-5, after initial production).

8. **Ancillary Facilities:**

Please see the Natural Buttes SOP.

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Location size may change prior to the drilling of the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling rig. The location will be re-surveyed and a form 3160-5 will be submitted.

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

A Diversion dam shall be constructed around the corner of the NE of the location as discussed at the on-site inspection.

The Diversion ditches shall be installed to divert water around the corners of the location as discussed at the on-site inspection.

A Erosion Dam shall be constructed NE of the location as discussed at the on-site inspection.

If plastic reinforced liner is used, it will be a minimum 12 mil thick, with sufficient bedding used to cover any rocks (Felt & Straw). The liner will overlap the pit walls and be covered with dirt and/or rock to hold it in place. No trash or scrap that could puncture the liner will be do disposed of in the pit.

10. Plans for Reclamation of the Surface:

Please see the Natural Buttes SOP.

The following seed mixture will be used to reclaim the surface. A total of 12 lbs/acre will be used if seeds are drilled (24 lbs/acre if seeds are broadcast). The per acre requirements for drilled seeds are:

Needle & Thread	4 lbs.
Black Sage	2 lbs.
Shade Scale	3 lbs.
Indian Rice Grass	3 lbs.

11. Surface Ownership:

The well pad and access road are located on lands owned by:

United State of America
Bureau of Land Management
170 South 500 East
Vernal, Utah 84078
(435)781-4400

12. Other Information:

A Class III archaeological survey was conducted by Metcalf Archaeological Consultants is attached.

This location is not within 460 feet from the boundary of the Natural Buttes Unit, nor is it within 460 feet of any non-committed tract lying within the boundaries of the Unit.

13. Lessee's or Operators's Representative & Certification:

Cheryl Cameron
Sr. Regulatory Analyst
Coastal Oil & Gas Corporation
P.O. Box 1148
Vernal, UT 84078
(435) 781-7023

Darrell Molnar
Drilling Manager
Coastal Oil & Gas Corporation
9 Greenway Plaza, Suite 2775
Houston, TX 77046-0995
(713) 418-4295

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

Coastal Oil & Gas Corporation is considered to be the operator of the subject well. Coastal Oil & Gas Corporation agrees to be responsible under the terms and conditions of the lease for the operations conducted upon leased lands.

Bond Coverage pursuant to 43 CFR 3104 for lease activities is being provided by Coastal Oil & Gas Corporation Bond #102103, BLM Nationwide Bond #U-605382-9, and BIA Nationwide Bond #114066-A.


The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

/s/ Cheryl Cameron
Cheryl Cameron



4/5/01
Date



LEGEND:

○ PROPOSED LOCATION

N

COASTAL OIL & GAS CORP.

NBU #336

SECTION 4, T10S, R22E, S.L.B.&M.

515' FNL 2134' FEL

UEIS


Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

8 25 98
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: C.G. REVISED: 00-00-00

A
TOPO



LEGEND:

--- PROPOSED ACCESS ROAD
--- EXISTING ROAD

COASTAL OIL & GAS CORP.

NBU #336
 SECTION 4, T10S, R22E, S.L.B.&M.
 515' FNL 2134' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
 MAP

8 31 98
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.G. REVISED: 2-21-01

B
 TOPO



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- WATER WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

COASTAL OIL & GAS CORP.

NBU #336
SECTION 4, T10S, R22E, S.L.B.&M.
515' FNL 2134' FEL

U
E
S


Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

8 **25** **98**
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.G. REVISED: 00-00-00

C
TOPO



APPROXIMATE TOTAL PIPELINE DISTANCE = 1800' +/-

LEGEND:

- — — — — EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- — — — — PROPOSED ACCESS



COASTAL OIL & GAS CORP.

NBU #336

SECTION 4, T10S, R22E, S.L.B.&M.

515' FNL 2134' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**

8 31 98
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: C.G. REVISED: 00-00-00

**D
TOPO**

COASTAL OIL & GAS CORP.

LOCATION LAYOUT FOR


NBU #336
SECTION 4, T10S, R22E, S.L.B.&M.
515' FNL 2134' FEL

SCALE: 1" = 50'

DATE: 8-26-98

Drawn By: C.B.T.

Revised: 02-20-01 D.R.B.




COASTAL OIL & GAS CORP.

TYPICAL CROSS SECTIONS FOR

NBU #336



SECTION 4, T10S, R22E, S.L.B.&M.

515' FNL 2134' FEL




DATE: 8-26-98


Drawn By: C.B.T.




STA. 3+25



STA. 1+50



STA. 0+55



STA. 0+00

FIGURE #2

APPROXIMATE YARDAGES

CUT	
(6") Topsoil Stripping	= 1,140 Cu. Yds.
Remaining Location	= 9,610 Cu. Yds.
TOTAL CUT	= 10,750 CU.YDS.
FILL	= 3,480 CU.YDS.



EXCESS MATERIAL AFTER 5% COMPACTION	= 7,090 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 2,480 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 4,610 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING

85 South 200 East Vernal, Utah

3,000 PSI

BOP STACK





M A C

Metcalf Archaeological Consultants, Inc.

DENVER DISTRICT - E & S

OCT 19 1998

October 16, 1998

BLC _____ RAD _____ SCP _____ CEL _____
SAB AD JRN _____ MDE _____ LPS _____

XC: PUL
PER


Ms. Sheila Bremmer
Coastal Oil & Gas Corp.
P. O. Box 749
Denver, CO 80201-0749

Dear Ms. Bremmer:

Enclosed is Metcalf Archaeological Consultants, Inc. (MAC) cultural resource inventory report covering ten proposed well projects for Coastal Oil & Gas in Uintah County, Utah. A single prehistoric isolate was recorded during these inventories. Since no significant cultural resources were discovered during these inventories, cultural resource clearance is being recommended for all ten projects.

If you have any questions or need further assistance please do not hesitate to contact us.

Sincerely,


Michael D. Metcalf
Principal Investigator

MDM/sjm

Enclosure

cc: Blaine Phillips, BLM Vernal District, Vernal



COVER PAGE

Must Accompany All Project Reports
Submitted to Utah SHPO

Project Name: Ten Projects for Coastal Oil & GasState Proj. No. U-98-MM-0490bReport Date: October 1998Principal Investigator: Michael D. MetcalfField Supervisor(s): Lauri TravisAcreage Surveyed 164.9Intensive: 164.9 acres

Recon/Intuitive: _____ acres

7.5' Series USGS Map Reference(s): Big Pack Mtn. NE and Archy Bench

Sites Reported	Count	Smithsonian Numbers
Archaeological Sites		
Revisits (no inventory form update)	<u>0</u>	_____
Revisits (Update IMACS site inventory form attached)	<u>0</u>	_____
New recordings (IMACS site inventory form attached)	<u>0</u>	_____
Total Count of Archaeological Sites	<u>0</u>	
Hist. Structures(USHS 106 Site info form atchd)	<u>0</u>	
Total National Register Eligible Sites	<u>0</u>	

Checklist of Required Items

1. X 1 Copy of the final report
2. X Copy of 7.5' Series USGS Map with Surveyed/Excavated Area Clearly Identified.
3. Completed IMACS Site Inventory Forms, Including
____Parts A and B or C,
____the IMACS encoding Form,
____Site Sketch Map,
____Photographs, and
____Copy of the Appropriate 7.5' Series USGS Map w/ the Site Location Clearly Marked and Labeled w/ the Smithsonian Site Number
4. X Completed "Cover Sheet" Accompanying Final Report and Survey Materials

Ten Well Pad Projects for Coastal Oil & Gas Company:
Class III Cultural Resource Inventory,
Uintah County, Utah

by
Lauri Travis
Metcalf Archaeological Consultants, Inc.
P.O. Box 10504
Helena, MT 59604

prepared for
Coastal Oil & Gas Company

Bureau of Land Management
Cultural Resources Permit # 98-UT-54945
expires May 1, 1999

October 1998
Project No. U-98-MM-0490b

Introduction

Metcalf Archaeological Consultants, Inc. (MAC) was contacted by Coastal Oil and Gas Company to perform a Class III cultural resource inventory of ten proposed well locations and access roads in Uintah County, Utah. The well locations are listed in Table 1, including legal location, footage, total acreage covered, access road distance and direction, and pipeline distance and direction. Figures 1, 2, 3 and 4 illustrate well locations plotted on 7.5' USGS quadrangle maps.

These cultural resource inventories were conducted to maintain compliance with the National Historic Preservation Act, as amended. The proposed well locations and access roads will be located on land administered by the Bureau of Land Management (BLM), Vernal District Office, Vernal, Utah. The purpose of the inventories was to locate and record cultural resources within the area of potential effect (APE) of the proposed well locations and access roads. If cultural resources were found, their locations were recorded, the appropriate state forms were completed (IMAC), a sketch map was made, and photographs were taken. Cultural resources would then be evaluated for eligibility to the National Register of Historic Places (NRHP), and recommendations concerning their management would be discussed.

On August 18 through the 22, and August 24, 1998, Lauri Travis, staff archaeologist with Metcalf Archaeological Consultants, Inc., performed cultural resource inventories for ten proposed well pads and access roads. The well locations, access and pipeline locations were staked at the time of the survey. All field notes and other pertinent data are on file at Metcalf Archaeological Consultants, Inc. Helena, MT branch.

Management Summary

The cultural resources inventory of the proposed well locations and access revealed one isolated find. The isolated find was located on the proposed access road to CIGE #242-33-9-22. This isolated find is not considered eligible for the National Register of Historic Places. No previously recorded sites are located in or near the vicinity of any proposed well locations, road access or pipelines. Cultural resource clearance is recommended for the ten proposed wells, access and pipelines as staked at the time of the survey and depicted in Figures 1, 2 and 3.

Effective Environment

The project area is located in the Uinta Basin physiographic subdivision of Utah (Stokes 1977). All proposed well locations are a few miles east of the White River in an

Table 1**Well Locations and Accompanying Information**


<u>Well</u>	<u>Legal T/R/S</u>	<u>Footage</u>	<u>Acres Dis/Dir</u>	<u>Pipeline Dis/Dir</u>	<u>Acres</u>
NBU-332	10S 21E/10	2036FSL 914FWL	200m SW	240m NE	13.3
CIGE 242-33-9-22	9S 22E/33	1332FNL 940FWL	300m N	750m W	17.8
CIGE 243-33-9-22	9S 22E/33	1798FSL 962FWL	400m S	630m SW	17.7
NBU-327	9S 22E/33	720FSL 1465FEL	350m NE	360m E	15.2
NBU-329	10S 22E/1	1527FSL 1994FWL	300m E	650m E	16.9
CIGE 248-21-10-21	10S 21E/21	2197FSL 834FWL	500m E	1900m NE	28.0
NBU-330	10S 21E/3	752FNL 570FEL	150m SE	350m N	13.7
NBU-331	10S 21E/3	500FNL 1800FEL	75m NE	450m N	13.8
NBU-336	10S 22E/4	515FNL 2134FEL	350m S	500m E	16.3
NBU-335	10S 22E/4	2032FNL 580FEL	150m E	150m NW	12.2
Total Acres					164.9

area of high ridges and deeply incised drainages. Geology of the area is dominated by the Eocene Uintah Formation and is often overlain by alluvial surficial deposits. Occasional outcrops of the Green River Formation may also be present (Hintze 1980). Local vegetation is predominantly the sagebrush community, including low sagebrush, bunch grasses, saltbush, prickly pear cactus, Mormon Tea, and forbs. Specific well and access locations are discussed below.

NBU-332

T10S R21E Section 10 2036 FSL 914 FWL

The proposed well is located on a gentle north sloping plain with two small intermittent drainages traversing in a southeast-northwest direction through the area. Both drainages are about a foot deep throughout the well pad location. The sagebrush community is dominant, but sparse. Ground surface visibility is very good at 80-90%. Soils are a silty



BIG PACK MTN. NE, UTAH
39109-H5-TF-024

1968
PHOTOREVISED 1987
DMA 4063 I NE-SERIES V897

T10S R21E

CIGE 248-21-10-21



proposed access


proposed pipeline


21

22

28

27





brown loam with many tan-red sandstone outcrops. The area appears to have little soil deposition except at the slope toes. The access road starts at the southwest end of the proposed pad and extends approximately 200 meters to an existing road. The proposed pipeline runs east about 240 meters from the northeast side of the proposed pad to tie into an existing pipeline.

NBU-327

T9S R22E Section 33

720 FSL 1465 FEL

This proposed location is on top of a knoll overlooking an intermittent drainage 300 meters to the northwest. The sagebrush community prevails and ground surface visibility is between 60 to 90%. Soil on the top of the knoll is a tan sandy loam with heavy accumulations on the southeast side. The northwest side of the knoll has been heavily deflated with red sandstone bedrock exposed in many areas. The access road begins at the northeast side of the proposed well and runs northeast about 350 meters to tie in at an existing road. The proposed pipeline begins along the southwest side of the pad and runs southwest for about 60 meters then turns sharply east and continues for 300 meters to tie in with an existing pipeline.

NBU-329

T10S R22E Section 1

1527 FSL 1994 FWL

Proposed well NBU-329 is located at the base of a large sandstone outcrop. The large sandstone outcrop is abutted by the proposed well pad to the southwest. The outcrop is about 100 meters east-west, 50 meters north-south and 30 meters tall. Vegetation is dominated by the sagebrush community but some greasewood is present as well. Surface visibility is fairly good at 60-80%. Soil in the area is a tan sandy loam which does not appear to be sand dunes or sand shadows, but a thin layer on top of residual soils. The road access runs from the east side of the proposed well pad about 300 meters east to join existing well NBU-211. The proposed feeder pipeline runs 630 meters east from the east side of the proposed pad to tie in with an existing pipeline. The first 250 meters of the feeder pipeline parallels an existing aboveground pipeline.

CIGE 248-21-10-21

T10S R21E Section 21

2197 FSL 834 FWL

Proposed location is on a small knoll and north slope of knoll overlooking an intermittent drainage 100 meters to the north. Vegetation is sagebrush community with surface visibility around 70-90%. There is little soil deposition on top of the siltstone cobble bedrock formation. At least 80% of the ground surface is covered with angular siltstone cobbles. Soils that are present are silty red loams. The proposed access road leaves the south side of the pad and continues for about 50 meters south then turns sharply east to skirt around a butte for about 450 meters to tie into an existing road. The proposed

pipeline parallels the proposed road access to this point. The proposed pipeline then continues northeast paralleling the existing road and an aboveground pipeline for approximately 1900 meters to tie in at existing well CIGE-58.

CIGE 243-33-9-22

T9S R22E Section 33

1798 FSL 962 FWL

Proposed location is on top of a bluff with steep (25-35%) slopes overlooking the White River about one mile east. Vegetation is sagebrush community with 60-90% ground surface visibility. The top of the bluff is covered with rounded and worn tan sandstone outcrops. Outcrops are very weathered and much of the stone is exfoliated. There is very little sand deposition overlying the bedrock. The proposed road access runs about 400 meters south, including a large east-west bend in the stretch. The road access ties in at existing well CIGE-64D. The proposed pipeline runs about 630 meters southwest to the tie-in area.

CIGE 242-33-9-22

T9S R22E Section 33

1332 FNL 940 FWL

Proposed well pad is located on the south end of a small bench overlooking the White River about one and a half miles to the east. Lower areas of the bench have exposed angular siltstone with some sand accumulations at the toe of the slopes. Higher areas on top of the bench contain exposed rounded sandstone outcrops with little sand overlying the bedrock. This entire area has little deposition, just a few sand accumulation belts along slope areas. Vegetation of the sage community is sparse leading to good ground visibility, around 80-90%. Road access runs approximately 300 meters. The road runs from the west side of the proposed well pad at the top of the bench and continues west for about 70 meters, then turns quickly north for 230 meters to tie-in near the existing CIGE-190 well. The proposed pipeline leaves the east side of the well pad and sharply turns north for 50 meters. The pipeline then travels northwest for 200 meters and finally sharply to the west for about 300 meters. From this point, the pipeline turns due north for 200 meters to tie in at an existing aboveground pipeline.

NBU-330

T10S R21E Section 3

752 FNL 570 FEL

NBU-330 is located on a south facing slope up against a large sandstone outcrop to the north. An intermittent drainage is 10 meters west of the proposed well pad. The vegetation present is the sagebrush community with the addition of Mormon Tea. Ground surface visibility is 50-80%. Deposition of the area is depicted by sand dunes with a few blow out areas on the northern periphery. Cuts along the intermittent drainage to the west indicate deposition of the area is at least 70 centimeters. Rodent activity in the area is moderate to high and does not demonstrate any evidence of buried deposits. Outcrops of

bedrock are visible throughout the area, especially in the northern border. The road access leaves the pad on the south side and continues approximately 150 meters southeast to an existing road. The proposed pipeline leaves the pad on the north side and continues north for about 350 meters and ties in near existing well CIGE-236.

NBU-331

T10S R21E Section 3 500 FNL 1800 FEL

Proposed well location is on a gentle northeast sloping plain surrounded by small ridges to the north and west. Proposed location is on a deflated plain with little deposition. A few areas do contain very small dune accumulations, a meter or two in diameter. The dunes appear to have little depth, half a meter to a meter, as shown by erosion and the deflated surrounding areas. Dominant vegetation is the sagebrush community and surface visibility is 50-80%. Soils are tan sandy loams overriding a red sandstone bedrock. The proposed access road runs about 75 meters northeast to tie into an existing road. The proposed pipeline runs north about 450 meters to the tie-in area. The pipeline will run up a steep hill and over a ridge and ties in at the top of the ridge.

NBU-336

T10S R22E Section 4 515 FNL 2134 FEL

This well is to be located southeast of a large butte with sandstone outcroppings. The proposed pad is located at the toe of the butte, directly up against the steep slope. Two small drainages flow south off the butte through the proposed pad area. The well area does not have sand accumulations, only a thin layer of residual silty loams. About 70% of the surface is covered with sandstone and siltstone cobbles. Vegetation is dominated by the sage community with greasewood and pickleweed gathering near the drainages indicating a probable high salt content in the soil. Ground visibility is between 50 and 80%. The road access alignment proceeds 350 meters south to well NBU-67. The proposed pipeline tie-in is approximately 500 meters east.

NBU-335

T10S R22E Section 4 2032 FNL 580 FEL

NBU-335 is located on a gentle northwest slope of a small butte. A small ridge trending east-west is present on the southern edge of the proposed well pad. Sandstone and siltstone cobbles cover about 50% of the surface. Soils are mostly tan silty loams overlying the sandstone bedrock. There are very few sand dune accumulations in small patches of one meter in diameter. These dunes have been highly disturbed by rodent activities and reveal no evidence of buried cultural remains. Vegetation is predominantly the sagebrush community and ground visibility is 50-80%. The proposed road access alignment extends about 150 meters east to an existing road. The pipeline runs about 150 meters northwest to an existing pipeline.

Files Search

A file search was requested from the Cultural Records Office of the Utah State Historic Preservation Office on July 7, 1998. A second file search was conducted at the Bureau of Land Management (BLM), Vernal District Office on August 18, 1998. The file search results are summarized in Table 2. Twenty-one inventories were previously conducted within the project areas. All projects included both linear and block surveys as all projects were well and access roads.

Four sites have been previously recorded. Three of the sites remain unevaluated and one is not eligible for the National Register of Historic Places. None of the four sites are located in the proposed well or access areas. Previously recorded 42UN1792 is located over a half mile northeast of the proposed NBU-332 location. 42UN657, 42UN1895 and 42UN1852 are all located several hundred meters northeast of proposed well locations CIGE 242-33-9-22 and CIGE 243-33-9-22.

Methods

The ten proposed Coastal Oil & Gas Company well locations, access roads and pipelines were plotted on USGS 7.5' quadrangle maps then surveyed for any cultural resources. The access roads and proposed pipelines were investigated by walking two zigzag transects, one on each side of the center stakes, so that a total coverage of 50 feet on each side of the center stakes was inventoried. The well location was covered as a ten-acre block centered on the well center stake and oriented to the cardinal directions. The well pad area was investigated by walking parallel transects with spacing between transects no more than fifteen meters. A few zones within the project areas had received disturbance from rodent activities or heavy erosion. These areas were carefully inspected for signs of buried deposits. One isolated find was observed within the proposed road access to CIGE-242-33-9-22.

Results

One isolated find (IF-1) was observed in the proposed access road location for CIGE 242-33-9-22, about 120 meters west of the well pad location. The isolated find consisted one black chert primary flake. The isolated find is not considered eligible for inclusion on the NRHP. No previously recorded cultural resources are found in the project areas. Visibility and conditions for site discovery were adequate at the time of

Table 2.
Files Search Summary

(T/R/sec) Legals	Project Description	Project Type	Consultant	Result(NRHP)
10S/21E/3	Coastal NBU-101	lineal/block	MM	-----
10S/21E/3	Coastal CIGE-135	lineal/block	MM	-----
10S/21E/3	Coastal CIGE-166-3-10-21	lineal/block	MM	-----
10S/21E/3	Colo. Interstate F-362	lineal/block	MM	-----
10S/21E/10	Coastal CIGE-139	lineal/block	MM	42UN1792(U)
10S/21E/10	Coastal CIGE-151-10-10-21	lineal/block	MM	-----
10S/21E/10	Coastal NBU-179	lineal/block	MM	-----
10S/21E/21	Bitter Creek Gas Field	lineal/block	AERC	-----
9S/22E/33	Coastal NBU-138-A	lineal/block	MM	42UN657(U) 42UN1852(U)
9S/22E/33	Coastal CIGE-152-33-9-22	lineal/block	MM	-----
9S/22E/33	Coastal NBU-173	lineal/block	MM	42UN1895(NE)
9S/22E/33	Coastal CIGE-174	lineal/block	MM	-----
9S/22E/33	Colo. Interstate F-364	lineal/block	MM	-----
9S/22E/33	Coastal NBU-112	lineal/block	MM	-----
10S/22E/4	Coastal NBU-209	lineal/block	MM	-----
10S/22E/4	Coastal NBU-67	lineal/block	MM	-----
10S/22E/4	Coastal NBU-147	lineal/block	MM	-----
10S/22E/4	Coastal NBU-148	lineal/block	MM	-----
10S/22E/4	Coastal NBU-170	lineal/block	MM	-----
10S/22E/4	Coastal NBU-208	lineal/block	MM	-----
10S/22E/4	Colo. Interstate F-359	lineal/block	MM	-----

Consultants:

AERC Archaeological-Environment Resource Corp.
MM Metcalf Archaeological Consultants, Inc.

NRHP eligibility:

NE not eligible
E eligible(SHPO
concurrence)
U unevaluated

survey. Cultural resource clearance is recommended for all ten proposed well pads, access roads and pipelines, as staked at the time of survey. No further work is recommended.

References Cited

Hintze, L.

1980 Geologic Map of Utah. Dept.of Natural Resources, Utah Geological and Mineral Survey, Salt Lake City.

Stokes, M.

1977 Physiographic Subdivisions of Utah. Dept.of Natural Resources, Utah Geological and Mineral Survey, Salt Lake City.

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 04/13/2001

API NO. ASSIGNED: 43-047-34027

WELL NAME: NBU 336

OPERATOR: COASTAL OIL & GAS CORP (N0230)

CONTACT: CHERYL CAMERON

PHONE NUMBER: 435-781-7023

PROPOSED LOCATION:

NWNE 04 100S 220E

SURFACE: 0515 FNL 2134 FEL

BOTTOM: 0515 FNL 2134 FEL

UINTAH

NATURAL BUTTES (630)

LEASE TYPE: 1 - Federal

LEASE NUMBER: U-01191

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: WSTC

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. U-605382-9)

☒ Potash (Y/N)

☒ Oil Shale (Y/N) *190-5 (B) or 190-3

☒ Water Permit
(No. 43-8496)

☒ RDCC Review (Y/N)
(Date:)

☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

 R649-2-3. Unit NATURAL BUTTES

 R649-3-2. General

 Siting: 460 From Qtr/Qtr & 920' Between Wells

 R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 173-14


Eff Date: 12-2-99

Siting: 460' f. Unit Boundary & Uncomm. Lands.

 R649-3-11. Directional Drill

COMMENTS: NBU SOP, separate file.

STIPULATIONS: ① FEDERAL APPROVAL
② OIL SHALE




Utah Oil Gas and Mining

OPERATOR: COASTAL O&G CORP (N0230)

SEC. 4, T10S, R22E

FIELD: NATURAL BUTTES (630)

COUNTY: UINTAH UNIT: NATURAL BUTTES
CAUSE: 173-14



PREPARED BY: LCORDOVA
DATE: 17-APRIL-2001



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Kathleen Clarke
Executive Director

Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
801-538-5340
801-359-3940 (Fax)
801-538-7223 (TDD)

April 18, 2001

Coastal Oil & Gas Corporation
PO Box 1148
Vernal, UT 84078

Re: Natural Buttes Unit 336 Well, 515' FNL, 2134' FEL, NW NE, Sec. 4, T. 10 South,
R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-34027.

Sincerely,

A handwritten signature in black ink, appearing to read 'John R. Baza'.

John R. Baza
Associate Director

er
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Coastal Oil & Gas Corporation

Well Name & Number Natural Buttes Unit 336

API Number: 43-047-34027

Lease: U 01191

Location: NW NE **Sec.** 4 **T.** 10 South **R.** 22 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

- 4.** In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.

- 5.** State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER _____

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

8 South 1200 East CITY Vernal STATE Utah ZIP 84078

PHONE NUMBER:

435-789-4433

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

COUNTY:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Name Change</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation

NAME (PLEASE PRINT) John T. Elzner

TITLE Vice President

SIGNATURE

DATE 06-15-01

El Paso Production Oil & Gas Company

NAME (PLEASE PRINT) John T. Elzner

TITLE Vice President

SIGNATURE

DATE 06-15-01

(This space for State use only)

RECEIVED

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING

State of Delaware
Office of the Secretary of State

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

MAR 11 2001

DIVISION OF
OIL, GAS AND MINING



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

0610204 8100

AUTHENTICATION: 1061007

010162788

DATE: 04-03-01

CERTIFICATE OF AMENDMENT

OF

CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:

"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION



David L. Siddall
Vice President

Attest:


Margaret E. Roark, Assistant Secretary

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

JUL 12 2001

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:
3106
UTSL-065841
(UT-924)

JUL 10 2001

NOTICE

El Paso Production Oil & Gas Company : Oil and Gas
Nine Greenway Plaza :
Houston TX 77046-0095 :

Name Change Recognized


Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.



Opolonia L. Abeyta
Acting Chief, Branch of
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
~~State of Utah, DOGM~~, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

Exhibit of Leases

UTUSL-065841A	UTU-47172	UTU-74415	UTU-53860
UTU-28652	UTU-50687	UTU-74416	UTU-66401
UTU-37943	UTU-52298	UTU-75091	UTU-67868
UTU-44089	UTU-0109054	UTU-75096	UTU-65389
UTU-44090A	UTU-0143511	UTU-75097	UTU-77084
UTU-61263	UTU-0143512	UTU-75673	UTU-61430
UTU-00343	UTU-38401	UTU-76259	UTU-72633
UTU-02651	UTU-38411	UTU-76260	UTU-72650
UTU-02651B	UTU-38418	UTU-76261	UTU-49692
UTU-0142175	UTU-38419	UTU-76493	UTU-57894
UTU-70235	UTU-38420	UTU-76495	UTU-76829
UTU-70406	UTU-38421	UTU-76503	UTU-76830
UTU-74954	UTU-38423	UTU-78228	UTU-76831
UTU-75132	UTU-38424	UTU-78714	
UTU-75699	UTU-38425	UTU-78727	
UTU-76242	UTU-38426	UTU-78734	
UTU-78032	UTU-38427	UTU-79012	
UTU-4377	UTU-38428	UTU-79011	
UTU-4378	UTU-53861	UTU-71694	
UTU-7386	UTU-58097	UTU-00576	
UTU-8344A	UTU-64376	UTU-00647	
UTU-8345	UTU-65222	UTU-01470D	
UTU-8347	UTU-65223	UTU-0136484	
UTU-8621	UTU-66746	UTU-8344	
UTU-14646	UTU-67178	UTU-8346	
UTU-15855	UTU-67549	UTU-8648	
UTU-25880	UTU-72028	UTU-28212	
UTU-28213	UTU-72632	UTU-30289	
UTU-29535	UTU-73009	UTU-31260	
UTU-29797	UTU-73010	UTU-33433	
UTU-31736	UTU-73013	UTU-34711	
UTU-34350	UTU-73175	UTU-46699	
UTU-34705	UTU-73434	UTU-78852	
UTU-37116	UTU-73435	UTU-78853	
UTU-37355	UTU-73444	UTU-78854	
UTU-37573	UTU-73450	UTU-075939	
UTU-38261	UTU-73900	UTU-0149767	
UTU-39223	UTU-74409	UTU-2078	
UTU-40729	UTU-74410	UTU-44426	
UTU-40736	UTU-74413	UTU-49530	
UTU-42469	UTU-74414	UTU-51026	

OPERATOR CHANGE WORKSHEET**ROUTING**

1. GLH		4-KAS
2. CDW	✓	5-LP ✓
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X **Merger**The operator of the well(s) listed below has changed, effective: **3-09-2001**

FROM: (Old Operator):
COASTAL OIL & GAS CORPORATION
Address: 9 GREENWAY PLAZA STE 2721
HOUSTON, TX 77046-0995
Phone: 1-(713)-418-4635
Account N0230

TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY
Address: 9 GREENWAY PLAZA STE 2721 RM 2975B
HOUSTON, TX 77046-0995
Phone: 1-(832)-676-4721
Account N1845

CA No.**Unit: NATURAL BUTTES****WELL(S)**

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 519-3E	43-047-33779	2900	03-09S-21E	FEDERAL	GW	P
NBU 368	43-047-33972	99999	04-09S-21E	FEDERAL	GW	APD
CIGE 256	43-047-33971	2900	09-09S-21E	FEDERAL	GW	APD
CIGE 242	43-047-34022	99999	33-09S-22E	FEDERAL	GW	APD
NBU 288	43-047-32986	2900	03-10S-22E	FEDERAL	GW	P
NBU 336	43-047-34027	99999	04-10S-22E	FEDERAL	GW	APD
NBU 337	43-047-34020	99999	04-10S-22E	FEDERAL	GW	APD
NBU 338	43-047-34058	99999	05-10S-22E	FEDERAL	GW	APD
NBU 344	43-047-34021	99999	08-10S-22E	FEDERAL	GW	APD
NBU 348	43-047-34001	99999	11-10S-22E	STATE	GW	APD
NBU 349	43-047-34002	99999	11-10S-22E	STATE	GW	APD
NBU 382	43-047-34235	99999	22-10S-22E	FEDERAL	GW	NEW
NBU 381	43-047-34234	99999	23-10S-22E	FEDERAL	GW	NEW
NBU 39	43-047-30861	2900	29-10S-22E	FEDERAL	GW	P
NBU 360	43-047-33773	2900	29-10S-22E	FEDERAL	GW	P
NBU 47N2	43-047-30534	2900	30-10S-22E	FEDERAL	GW	S
NBU 351	43-047-33668	2900	30-10S-22E	FEDERAL	GW	P
NBU 384	43-047-34237	99999	30-10S-22E	FEDERAL	GW	NEW
NBU 70-34B	43-047-30577	2900	34-10S-22E	FEDERAL	GW	S
NBU 62-35B	43-047-30477	2900	35-10S-22E	FEDERAL	GW	S

OPERATOR CHANGES DOCUMENTATION

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
- The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
- Is the new operator registered in the State of Utah: YES Business Number: 608186-0143

5. If **NO**, the operator was contacted on: N/A
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 07/10/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 07/10/2001
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: N/A
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 08/23/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 08/23/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: N/A

FEDERAL BOND VERIFICATION:

1. Federal well(s) covered by Bond No.: WY 2793

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond No: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

FILMING:

1. All attachments to this form have been **MICROFILMED** on: _____

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: _____

COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Coastal Oil & Gas Corporation

Well Name & Number: NBU #336

API Number: 43-047-34027

Lease Number: U - 01191

Location: NWNE Sec. 04 T. 10S R. 22E

Agreement: NATURAL BUTTES UNIT

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Casing Program and Auxiliary Equipment

As a minimum, the usable water and other mineral resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above base of the usable water zone, identified at $\pm 1,050$ ft.

B. SURFACE USE PROGRAM

-One water diversion dam will be constructed as shown on the cut sheet, and another erosion dam shall be constructed below the well location. The dirt contractor shall call Byron Tolman (781-4482) with the Vernal BLM Field Office when the dirt work is started so he can meet with the contractor to show him where the dam shall be constructed.

-The reserve pit topsoil shall be piled separate from the location topsoil as shown on the cut sheet.

-The location topsoil pile will be seeded immediately after the soil is piled by broadcasting the seed, then walking the topsoil pile with the dozer to plant the seed. The seed mix outlined in the APD for reclamation of the well will be used.

All poundages are in Pure Live Seed.

-The subsoil which is piled on the location is for the construction of tank dikes. **Topsoil will not be used for the construction of tank dikes.**

-Once the reserve pit is dry, it shall be filled, recontoured, topsoil spread, and seeded in the same manner discussed above.

JAN. 17. 2003 3:34PM

WESTPORT

NO. 173 P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5609

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Engineer Technician

Encl:



United States Department of the Interior

RECEIVED

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

El Paso Production Oil & Gas Company

3a. Address

P.O. Box 1148 Vernal, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NWNE Section 4-T10S-R22E 515'FNL & 2134'FEL

5. Lease Serial No.

U-01191

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

Natural Buttes Unit

8. Well Name and No.

NBU #336

9. API Well No.

43-047-34027

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- | | | | |
|---|---|--|--|
| <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other DOGM |
| <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon | APD Extension |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

The operator requests that the APD for the subject well be extended for an additional year so that drilling operations may be completed

RECEIVED

MAR 18 2002

DIVISION OF
OIL, GAS AND MINING

COPY SENT TO OPERATOR
Date: 03-26-02
Initials: [Signature]

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Sheila Upchego

Signature

Title

Regulatory Analyst

Date

March 14, 2002

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Approved by the
Utah Division of
Oil, Gas and Mining
Date: 03-26-02
By: [Signature]

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.

We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chrono





United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Washington, D.C. 20240

FEB 10 2003

IN REPLY REFER TO:
Real Estate Services

Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

Director, Office of Trust Responsibilities

ACTING

Enclosure

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE – Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

El Paso Production Oil & Gas Company

3a. Address

P.O. Box 1148 Vernal, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NWNE Section 4-T10S-R22E 515'FNL & 2134'FEL

5. Lease Serial No.

U-01191

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

Natural Buttes Unit

8. Well Name and No.

NBU #336

9. API Well No.

43-047-34027

10. Field and Pool, or Exploratory Area

Natural Buttes

11. County or Parish, State

Uintah County, Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other DOGM
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	<input type="checkbox"/> APD Extension
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

The operator requests that the APD for the subject well be extended for an additional year so that drilling operations may be completed

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: *03-03-03*
By: *[Signature]*

RECEIVED
FEB 24 2003
DIV. OF OIL, GAS & MINING

COPY SENT TO OPERATOR
Date: *03-03-03*
Initials: *CHD*

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Sheila Upchego

Title

Regulatory Analyst

Date

February 18, 2003

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 9 Greenway Plaza CITY Houston STATE TX ZIP 77064-0995 PHONE NUMBER: (832) 676-5933		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: COUNTY: QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		8. WELL NAME and NUMBER: Exhibit "A"
		9. API NUMBER:
		10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # _____

State Surety Bond No. RLB0005236
Fee Bond No. RLB0005238


EL PASO PRODUCTION OIL & GAS COMPANY

By: 
Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.	
NAME (PLEASE PRINT) David R. Dix	TITLE Agent and Attorney-in-Fact
SIGNATURE 	DATE 12/17/02

(This space for State use only)



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

February 27, 2003

Westport Oil and Gas Company, L.P.
Attn: Gary D. Williamson
1670 Broadway, Suite 2800
Denver, Colorado 80202

Re: Natural Buttes Unit
Uintah County, Utah

Gentlemen:

On February 27, 2003, we received an indenture dated December 17, 2002, whereby El Paso Production Oil & Gas Company resigned as Unit Operator and Westport Oil and Gas Company, L.P., was designated as Successor Unit Operator for the Natural Buttes Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 27, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Natural Buttes Unit Agreement.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover all operations within the Natural Buttes Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
SITLA
Division of Oil, Gas & Mining
Minerals Adjudication Group
File - Natural Buttes Unit (w/enclosure)
Agr. Sec. Chron
Fluid Chron

UT922:TAThompson:tt:02/27/2003

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

Form 3160-5
(August 1999)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 20005. Lease Serial No.
SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
SEE ATTACHED EXHIBIT "A"9. API Well No.
SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐
- Notice of Intent
-
- ☐
- Subsequent Report
-
- ☐
- Final Abandonment Notice

TYPE OF ACTION

- | | | | |
|---|---|--|---|
| <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other |
| <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon | SUCCESSOR OF |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | OPERATOR |

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed if testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

Approved by

THIS SPACE FOR FEDERAL OR STATE USE

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH	
2. CDW	✓
3. FILE	

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **12-17-02**

FROM: (Old Operator):	TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY	WESTPORT OIL & GAS COMPANY LP
Address: 9 GREENWAY PLAZA	Address: P O BOX 1148
HOUSTON, TX 77064-0995	VERNAL, UT 84078
Phone: 1-(832)-676-5933	Phone: 1-(435)-781-7023
Account No. N1845	Account No. N2115

CA No.

Unit:

NATURAL BUTTES

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 313	04-10S-22E	43-047-32838	2900	FEDERAL	GW	P
COG NBU 67	04-10S-22E	43-047-31737	2900	FEDERAL	GW	P
NBU 85J	04-10S-22E	43-047-31246	2900	FEDERAL	GW	P
NBU 46N	04-10S-22E	43-047-30513	2900	FEDERAL	GW	P
NBU 148	04-10S-22E	43-047-31983	2900	FEDERAL	GW	P
NBU 147	04-10S-22E	43-047-31984	2900	FEDERAL	GW	S
NBU 335	04-10S-22E	43-047-33727	2900	FEDERAL	GW	P
NBU 336	04-10S-22E	43-047-34027	99999	FEDERAL	GW	APD
NBU 337	04-10S-22E	43-047-34020	99999	FEDERAL	GW	APD
NBU 339	05-10S-22E	43-047-34406	2900	FEDERAL	GW	P
CIGE 281	05-10S-22E	43-047-34444	2900	FEDERAL	GW	P
NBU 338	05-10S-22E	43-047-34058	2900	FEDERAL	GW	P
NBU CIGE 52-5-10-22	05-10S-22E	43-047-30531	2900	FEDERAL	GW	P
NBU CIGE 73D-5-10-22P	05-10S-22E	43-047-30952	2900	FEDERAL	GW	S
NBU 140	05-10S-22E	43-047-31947	2900	FEDERAL	GW	P
NBU 149	05-10S-22E	43-047-31982	2900	FEDERAL	GW	S
NBU 242	05-10S-22E	43-047-32944	2900	FEDERAL	GW	P
NBU 171	05-10S-22E	43-047-32115	2900	FEDERAL	GW	P
CIGE 178-5-10-22	05-10S-22E	43-047-32330	2900	FEDERAL	GW	PA
NBU 280	05-10S-22E	43-047-34443	99999	FEDERAL	GW	APD

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
- The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
- Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- If **NO**, the operator was contacted contacted on: _____

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 03/24/2003
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 03/24/2003
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number RLB 0005238

2. The FORMER operator has requested a release of liability from their bond on: N/A

The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Multiple Wells - see attached

5. Lease Serial No.

Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

891008900A

8. Well Name and No.

Multiple Wells - see attached

9. API Well No.

Multiple Wells - see attached

10. Field and Pool, or Exploratory Area

Natural Buttes Unit

11. County or Parish, State

Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped. The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached. Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

J.T. Conley

Signature

COPY SENT TO OPERATOR
Date: 9-16-03
Initials: CHD

Title

Date

Operations Manager

SEP 10 2003

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Federal Approval of This Action is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Date: 9/16/03

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Westport Oil & Gas, L.P. Project Economics Worksheet

Instructions:

Fill in blue boxed areas with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name:

Condensate Shrinkage Economics

Is this job a well pull or production rig job ??? **N** (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0		\$0
WATER & HAULING		\$150	\$150
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350 Increased OPX Per Year

Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/860	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$ / HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

Production & OPX Detail:

	Before		After		Difference
Oil Production	0.192	BOPD	0.194	BOPD	0.002
Gas Production	0	MCFPD	0	MCFPD	0
Wtr Production	0	BWPD	0	BWPD	0
Horse Power		HP		HP	0
Fuel Gas Burned		MCFPD		MCFPD	0

Project Life:

Life = **20.0** Years
(Life no longer than 20 years)

Internal Rate of Return:

After Tax IROR = **#DIV/0!**

AT Cum Cashflow:

Operating Cashflow = **(\$2,917)** (Discounted @ 10%)

Gross Reserves:

Oil Reserves = **6 BO**
Gas Reserves = **0 MCF**
Gas Equiv Reserves = **38 MCFE**

Payout Calculation:

Payout = $\frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}}$ = 1


Payout occurs when total AT cashflow equals investment
See graph below, note years when cashflow reaches zero

Payout = **NEVER** Years or **#VALUE!** Days

Notes/Assumptions:

An average NBU well produces 0.192 Bcpd with no tank pressure. The production is increased to 0.194 Bcpd if 6 ozs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

WELL	LEGALS	STFLEASENO	CANUMBER	APINO
NBU 332	10-10-21 NWSW	UTU01416A	891008900A	430473364000S1
NBU 333	13-10-21 SWSW	ML23608	891008900A	430473364100S1 ✓
NBU 335	4-10-22 SENE	UTU01191	891008900A	430473372400S1
NBU 336	4-10-22 NWNE	U-01191	891008900A	430473402700S1
NBU 337	4-10-22 SENW	U-01191-A	891008900A	430473402000S1
NBU 338	5-10-22 NESE	UTU01191	891008900A	430473405800S1
NBU 339	5-10-22 NWSE	UTU01191	891008900A	430473440600S1
NBU 340	6-10-22 SWNE	UTU01195	891008900A	430473372500S1
NBU 340X	6-10-22 SWNE	UTU01195	891008900A	430473401500S1
NBU 341	6-10-22 SWNW	UTU464	891008900A	430473372600S1
NBU 342	7-10-22 NWSE	UTU468	891008900A	430473372700S1
NBU 343	8-10-22 NWNE	UTU01196C	891008900A	430473371900S1
NBU 344	8-10-22 SWNE	UTU01196C	891008900A	430473402100S1
NBU 345	10-10-22 SWNE	UTU02587	891008900A	430473370400S1 ✓
NBU 345-4E	4-10-21 SWSW	UTU01393B	891008900A	430473470000S1 ✓
NBU 347	11-10-22 NWSW	UTU01197A	891008900A	430473370900S1 ✓
NBU 348	11-10-22 SWSW	UTU01197A-ST	891008900A	430473400100S1
NBU 349	11-10-22 SWSE	UTU01197A-ST	891008900A	430473400200S1 ✓
NBU 350	14-10-22 NWNE	UTU01197A	891008900A	430473364200S1 ✓
NBU 351	30-10-22 SESE	UTU0132568A	891008900A	430473366800S1
NBU 352	9-9-21 SWNW	UTU0149767	891008900A	430473392200S1
NBU 353	27-9-21 SENW	U01194A	891008900A	430473320500S1 ✓
NBU 354	31-9-22 NENW	UTU464	891008900A	430473323100S1
NBU 356	30-9-22 NENW	U463	891008900A	430473323200S1
NBU 357	15-10-21 SWSW	UTU01791A	891008900A	430473372800S1
NBU 358	16-10-21 SESW	ML10755	891008900A	430473370800S1
NBU 359	29-10-21 NWNE	ML21330	891008900A	430473370600S1
NBU 360	29-10-22 SESW	UTU0145824	891008900A	430473377300S1
NBU 361	32-10-22 NWNW	ML22798	891008900A	430473370500S1 ✓
NBU 362	28-9-21 SESW	UTU0576	891008900A	430473377400S1
NBU 363	28-9-21 SESE	UTU0576	891008900A	430473377500S1
NBU 364	29-9-21 SESE	UTU0581	891008900A	430473377600S1
NBU 365	3-10-21 SESE	UTU0149078	891008900A	430473377700S1
NBU 366	10-10-21 NWNW	UTU0149079	891008900A	430473372900S1
NBU 367	11-10-22 NESW	UTU01197A-ST	891008900A	430473370700S1 ✓
NBU 370	17-9-21 NWSW	UTU0575	891008900A	430473467200S1 ✓
NBU 371	8-9-21 SWSE	UTU0575B	891008900A	430473467300S1 ✓
NBU 375	12-9-21 SWNE	UTU0141317	891008900A	430473444000S1 ✓
NBU 376	12-9-21 NENE	UTU0141317	891008900A	430473444100S1 ✓
NBU 377	31-9-21 NENW	UTU0582	891008900A	430473436300S1
NBU 378	31-9-21 NWNE	UTU0582	891008900A	430473436400S1
NBU 381	23-10-22 SESW	UTU01198B	891008900A	430473423400S1
NBU 382	22-10-22 SENW	U-01198-B	891008900A	430473423500S1
NBU 383	21-10-22 SESW	U-489	891008900A	430473423600S1
NBU 384	30-10-22 SENW	UTU0132568A	891008900A	430473423700S1 ✓
NBU 385	18-10-22 SENW	ML22973	891008900A	430473422800S1
NBU 386	17-10-22 NESE	UTU470	891008900A	430473423800S1
NBU 387	23-10-21 SWSE	U-02277-A	891008900A	430473423900S1
NBU 388	22-10-21 SENW	U-02278-A	891008900A	430473424000S1
NBU 389	28-10-21 NENE	ML21329	891008900A	430473422900S1
NBU 390	30-10-21 SESE	ML22793	891008900A	430473423000S1
NBU 391	17-9-21 NWNW	UTU0575	891008900A	430473487400S1
NBU 393	22-9-20 SWNW	U0577B	891008900A	430473486400S1
NBU 394	11-10-22 SWSE	UTU01197A-ST	891008900A	430473480400S1 ✓
NBU 395	27-9-21 SWSW	UTU01194A-ST	891008900A	430473437400S1 ✓
NBU 396	33-9-21 NENW	UTU0576	891008900A	430473448000S1 ✓
NBU 397	26-10-20 NESW	UTU4476	891008900A	430473436500S1
NBU 398	18-10-21 NENW	UTU02270A	891008900A	430473436600S1
NBU 399	14-10-21 NWNW	UTU465	891008900A	430473440900S1
NBU 400	16-10-21 NENW	ML10755	891008900A	430473479400S1
NBU 401	23-10-21 NENE	UTU02278A	891008900A	430473480100S1
NBU 404	32-9-22 SWSE	ML22649	891008900A	430473437500S1 ✓
NBU 405	27-9-21 NENE	UTU01194A-ST	891008900A	430473440700S1 ✓
NBU 407	32-10-22 NENW	ML22798	891008900A	430473431800S1 ✓
NBU 408	31-10-22 NENE	UTU0143551	891008900A	430473459000S1 ✓
NBU 409	32-9-21 NWSW	ML48758	891008900A	430473442100S1 ✓
NBU 410	32-9-21 SWSW	ML48758	891008900A	430473487200S1
NBU 411	32-9-21 SESE	ML48758	891008900A	430473442200S1 ✓
NBU 412	32-10-22 SENW	ML22798	891008900A	430473431900S1 ✓
NBU 413	32-10-22 SWNW	ML22798	891008900A	430473432000S1 ✓
NBU 414	31-10-22 SENE	UTU0143551	891008900A	430473438700S1
NBU 414-20E	20-9-21 NWNE	U0143551/U0575	891008900A	430473477900S1
NBU 415-20E	20-9-21 SWNE	UTU0575	891008900A	430473448900S1 ✓
NBU 416	36-9-20 SESE	ML48757	891008900A	430473442300S1 ✓
NBU 418	12-9-21 NWNW	UTU0141317	891008900A	430473477700S1



State of Utah

Department of
Natural Resources

Division of
Oil, Gas & Mining

ROBERT L. MORGAN
Executive Director

LOWELL P. BRAXTON
Division Director

MICHAEL O. LEAVITT
Governor

OLENE S. WALKER
Lieutenant Governor

January 20, 2004

Debra Domenici
Westport Resources Corp.
1368 South 1200 East
Vernal UT 84078

Re: APD Rescinded – NBU 336, Sec. 4, T. 10S, R. 22E
Uintah County, Utah API No. 43-047-34027


Dear Ms. Domenici:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on April 18, 2001. On March 26, 2002 and on March 3, 2003 the Division granted a one-year APD extension. On January 15, 2004 you requested that the division rescind the state approved APD. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective January 15, 2004.

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Whitney
Engineering Technician

cc: Well File
Bureau of Land Management, Vernal